

本 線

数 量 集 計 書

1.0式

工 種	名 称	規 格	条 件	単位	数 量	備 考
(舗装工)						
	表層工(AS)	t=50mm		m2	761	$675.3+85.5=760.8$
	表層工(CON)	t=100mm		m3	3	$24.7 \times 0.1 = 2.47$
	不陸整正			m2	761	$675.3+85.5=760.8$
	不陸整正(CON)			m2	25	24.7

市道亀ノ甲田野川橋線																	
数 量 計 算 書 (1)																	
測 点	単距離	表層 (AS)			表層 (CON)			不陸整正			不陸整正 (CON)			NO.			備 考
		断面積	平均断面	立 積	断面積	平均断面	立 積	断面積	平均断面	立 積	断面積	平均断面	立 積	断面積	平均断面	立 積	
NO. 5 + 10.000	0.000	6.46						6.46									
(SP. 1)																	
NO. 6	10.000	13.64	10.05	100.5	0.00		0.0	13.64	10.05	100.5	0.0	0.00	0.0				
NO. 7	20.000	6.80	10.22	204.4	0.75	0.38	7.6	6.80	10.22	204.4	0.75	0.38	7.6				
NO. 8	20.000	5.04	5.92	118.4	0.54	0.65	13.0	5.04	5.92	118.4	0.54	0.65	13.0				
NO. 8 + 7.685	7.685	5.00	5.02	38.6	0.54	0.54	4.1	5.00	5.02	38.6	0.54	0.54	4.1				
NO. 9	12.315	5.00	5.00	61.6				5.00	5.00	61.6							
NO. 9 14.000	14.000	10.62	7.81	109.3				10.62	7.81	109.3							
NO. 9 + 18.000	4.000	10.62	10.62	42.5				10.62	10.62	42.5							
NO.																	
NO. 6																	
NO. 7																	
NO. 8																	
(BC. 4)																	
NO. 8 + 7.685																	
NO. 9																	
NO. 9 + 14.000																	
NO. 10																	
NO. 10 + 5.000																	
(EC. 5)																	
NO. 10 + 12.088																	
合 計	88.000			675.3			24.7			675.3			24.7				

市道亀ノ甲田野川橋線					数 量 計 算 書 (2)													NO.
測 点	単距離	表層 (AS)			上層路盤			不陸整正			剥ぎ取り表土 W						備 考	
		断面積	平均断面	立 積	断面積	平均断面	立 積	断面積	平均断面	立 積	断面積	平均断面	立 積	断面積	平均断面	立 積		
1P 0	0.000	3.00						3.00										
1P 0 + 10.292	10.292	3.00	3.00	30.9				3.00	3.00	30.9								
1P 0 + 15.000	4.708	3.00	3.00	14.1				3.00	3.00	14.1								
1P 0 + 15.000	0.000			40.5						40.5							図面6/6	
合 計	15.000			85.5			0.0			85.5			0.0					