

数量総括表

	名称	規格	単位	算式	数量	備考
土工	掘削		m3	234.0	234	
	運搬	運搬距離 0.15km	m3	234.0	234	
	整地		m3	234.0	234	
構造物 撤去工	舗装版切断	アスファルト舗装版 15cm以下	m	$4.4+3.6=8.0$	8	P.0.0+P.600.0
	舗装版破碎	10cm以下	m2	2256.40	2,256.4	
	ダンプトラック運搬	アスファルト殻 DID区間無 L=7.1km	m3	$2256.4*0.04=90.3$	90.3	
	処分		m3	$2256.4*0.04=90.3$	90.3	
	カッター汚泥	運搬距離 108km	台		1.00	
	汚泥運搬		式		1.00	$0.023*0.04*8=0.007\text{m}^3$ $0.007*1.4\text{t}/\text{m}^3=0.01$
	処分		t		0.01	
舗装工	路盤工	100mm RM-30	m2	2256.40	2,256.4	
	表層工	再生密粒TOP13 40mm PK-3	m2	2256.40	2,256.4	
	区画線工		m		600	
仮設工	交通誘導警備員	交通誘導警備員B	人		68	

数量計算書

測点	延長	舗装取壊し			表層(t=40mm)			掘削		
		幅員	平均	面積(m2)	幅員	平均	面積(m2)	断面積	平均	立積(m3)
0		4.40			4.40			0.40		
20	20.0	4.30	4.35	87.00	4.30	4.35	87.00	0.40	0.40	8.00
40	20.0	3.50	3.90	78.00	3.50	3.90	78.00	0.40	0.40	8.00
60	20.0	3.10	3.30	66.00	3.10	3.30	66.00	0.30	0.35	7.00
80	20.0	3.50	3.30	66.00	3.50	3.30	66.00	0.40	0.35	7.00
100	20.0	3.20	3.35	67.00	3.20	3.35	67.00	0.30	0.35	7.00
120	20.0	3.40	3.30	66.00	3.40	3.30	66.00	0.30	0.30	6.00
140	20.0	3.75	3.58	71.60	3.75	3.58	71.60	0.40	0.35	7.00
160	20.0	3.70	3.73	74.60	3.70	3.73	74.60	0.40	0.40	8.00
180	20.0	3.90	3.80	76.00	3.90	3.80	76.00	0.40	0.40	8.00
200	20.0	3.70	3.80	76.00	3.70	3.80	76.00	0.40	0.40	8.00
220	20.0	3.70	3.70	74.00	3.70	3.70	74.00	0.40	0.40	8.00
240	20.0	3.90	3.80	76.00	3.90	3.80	76.00	0.40	0.40	8.00
260	20.0	3.90	3.90	78.00	3.90	3.90	78.00	0.40	0.40	8.00
280	20.0	3.60	3.75	75.00	3.60	3.75	75.00	0.40	0.40	8.00
300	20.0	4.00	3.80	76.00	4.00	3.80	76.00	0.40	0.40	8.00
320	20.0	3.30	3.65	73.00	3.30	3.65	73.00	0.30	0.35	7.00
340	20.0	3.50	3.40	68.00	3.50	3.40	68.00	0.40	0.35	7.00
360	20.0	3.85	3.68	73.60	3.85	3.68	73.60	0.40	0.40	8.00
380	20.0	5.80	4.83	96.60	5.80	4.83	96.60	0.60	0.50	10.00
400	20.0	3.50	4.65	93.00	3.50	4.65	93.00	0.40	0.50	10.00
420	20.0	3.70	3.60	72.00	3.70	3.60	72.00	0.40	0.40	8.00
440	20.0	3.30	3.50	70.00	3.30	3.50	70.00	0.30	0.35	7.00
460	20.0	3.50	3.40	68.00	3.50	3.40	68.00	0.40	0.35	7.00
480	20.0	3.50	3.50	70.00	3.50	3.50	70.00	0.40	0.40	8.00
500	20.0	3.70	3.60	72.00	3.70	3.60	72.00	0.40	0.40	8.00
520	20.0	4.00	3.85	77.00	4.00	3.85	77.00	0.40	0.40	8.00
540	20.0	4.00	4.00	80.00	4.00	4.00	80.00	0.40	0.40	8.00
560	20.0	4.00	4.00	80.00	4.00	4.00	80.00	0.40	0.40	8.00
580	20.0	4.00	4.00	80.00	4.00	4.00	80.00	0.40	0.40	8.00
600	20.0	3.60	3.80	76.00	3.60	3.80	76.00	0.40	0.40	8.00
合計	600.0			2256.40			2256.40			234.00