

林道日見須大成川線道路改良（舗装）工事

数 量 計 算 書

工 種	名 称	規 格 ・ 条 件	数 量	単位	備 考	
土工						
	掘削		220	m3	220.1	
	運搬	運搬距離 5.1 k m	220	m3	220.1	
	処分		220	m3	220.1	
舗装工						
	表層	平均幅員3.0m以上、40mm 再生密粒度アスコンTop (13)	2179.5	m2	2179.5	
	上層路盤	100mm RM-30	2179.5	m2	2179.5	
	区画線工		1050.0	m	1050.0	525.0m×2
構造物撤去工						
	舗装版切断	アスファルト舗装版 15cm以下	12.2	m	12.2	(P. 0. 0)L=1. 7 + (P. 100. 0)L=6. 0 + (P. 530. 0)L=4. 5
	舗装版破碎積込		2179.5	m2	2179.5	
	As殻運搬	運搬距離 6.3 k m	87.2	m3	87.18	2179.5*0.04
	As殻処分		87.2	m3	87.18	2179.5*0.04
	カッター汚泥運搬	運搬距離 99.3 k m	1	台	1	0.023*0.04*12.2=0.011m ³ 0.017*1.4 t /m ³ =0.0157
	カッター汚泥処分		0.02	t	0.0157	
仮設工						
	交通誘導警備員	B	66	人	66	33人×2ヶ所=66人

数 量 計 算 書 (1)														NO. 1
測点	単距離	舗装工			舗装版取壊			掘削						備 考
		幅	平均幅	面積	幅	平均幅	面積	断面積	平均断面	立 積	断面積	平均断面	立 積	
P. 0	0.000	14.1			14.1			1.4						
P. 7	7.000	4.9	9.50	66.5	4.9	9.50	66.5	0.5	0.95	6.7				
P. 20	13.000	4.0	4.45	57.9	4.0	4.45	57.9	0.4	0.45	5.9				
P. 39.4	19.400	4.0	4.00	77.6	4.0	4.00	77.6	0.4	0.40	7.8				
P. 39.4	0.000	4.0	4.00	0.0	4.0	4.00	0.0	0.4	0.40	0.0				控除
P. 74.5	35.100	4.0	4.00	0.0	4.0	4.00	0.0	0.4	0.40	0.0				控除
P. 74.5	0.000	4.0	4.00	0.0	4.0	4.00	0.0	0.4	0.40	0.0				
P. 80	5.500	4.0	4.00	22.0	4.0	4.00	22.0	0.4	0.40	2.2				
P. 100	20.000	5.2	4.60	92.0	5.2	4.60	92.0	0.5	0.45	9.0				
P. 120	20.000	5.6	5.40	108.0	5.6	5.40	108.0	0.6	0.55	11.0				
P. 140	20.000	4.0	4.80	96.0	4.0	4.80	96.0	0.4	0.50	10.0				
P. 160	20.000	4.0	4.00	80.0	4.0	4.00	80.0	0.4	0.40	8.0				
P. 180	20.000	4.0	4.00	80.0	4.0	4.00	80.0	0.4	0.40	8.0				
P. 200	20.000	4.0	4.00	80.0	4.0	4.00	80.0	0.4	0.40	8.0				
P. 220	20.000	4.0	4.00	80.0	4.0	4.00	80.0	0.4	0.40	8.0				
P. 240	20.000	4.0	4.00	80.0	4.0	4.00	80.0	0.4	0.40	8.0				
P. 260	20.000	4.0	4.00	80.0	4.0	4.00	80.0	0.4	0.40	8.0				
合	260.000			1000.0			1000.0			100.6				

数 量 計 算 書 (2)														NO. 2
測点	単距離	舗装工			舗装版取壊			掘削			断面積	平均断面	立 積	備 考
		幅	平均幅	面積	幅	平均幅	面積	断面積	平均断面	立 積				
P. 280	20.000	4.0	4.00	80.0	4.0	4.00	80.0	0.4	0.40	8.0				
P. 300	20.000	4.0	4.00	80.0	4.0	4.00	80.0	0.4	0.40	8.0				
P. 320	20.000	4.0	4.00	80.0	4.0	4.00	80.0	0.4	0.40	8.0				
P. 340	20.000	4.0	4.00	80.0	4.0	4.00	80.0	0.4	0.40	8.0				
P. 360	20.000	5.0	4.50	90.0	5.0	4.50	90.0	0.5	0.45	9.0				
P. 380	20.000	4.1	4.55	91.0	4.1	4.55	91.0	0.4	0.45	9.0				
P. 400	20.000	4.0	4.05	81.0	4.0	4.05	81.0	0.4	0.40	8.0				
P. 420	20.000	4.0	4.00	80.0	4.0	4.00	80.0	0.4	0.40	8.0				
P. 440	20.000	5.9	4.95	99.0	5.9	4.95	99.0	0.6	0.50	10.0				
P. 460	20.000	5.9	5.90	118.0	5.9	5.90	118.0	0.6	0.60	12.0				
P. 480	20.000	4.2	5.05	101.0	4.2	5.05	101.0	0.4	0.50	10.0				
P. 500	20.000	4.5	4.35	87.0	4.5	4.35	87.0	0.5	0.45	9.0				
P. 520	20.000	4.5	4.50	90.0	4.5	4.50	90.0	0.5	0.50	10.0				
P. 525	5.000	4.5	4.50	22.5	4.5	4.50	22.5	0.5	0.50	2.5				
合	525.000			2179.5			2179.5			220.1				