

数量計算書総括表

工 種	種 別	単位	計上数量	数 量	備 考
道路改良					
管理道舗装工					
(土工)					
機械掘削	床堀	m3	31	31.3	
機械埋戻	土砂	m3	140	135.7	
土砂運搬	L=4.5km以内	m3	71	70.7	
(舗装工)					
不陸整正		m2	1690	1689.0	
上層路盤工	再生粒調碎石RM-30 t=10cm	m2	1910	1912.6	As+Con舗装部
舗装工	再生密粒度As(13) t=4cm	m2	1690	1689.0	
コンクリート工	18-8-25(20) t=10cm	m3	22	22.4	
はけ引き仕上げ		m2	224	223.6	歩掛出典:公園緑地 施設仕上げ工 コンクリートハケ引き仕上げ
溶接金網	D6-150×150	m2	212	212.4	歩掛出典:林道 舗装工 溶接金網敷設
目地板	瀝青繊維質目地板 t=10mm	m2	2	1.6	
浄水場付帯工					
(土工)					
機械掘削	床堀	m3	20	19.5	
機械埋戻	土砂	m3	2	1.9	
土砂運搬		m3	17	17.3	舗装工にて計上
(浄水場内舗装工)					
コンクリート工	18-8-25(20) t=10cm	m3	16	16.0	
溶接金網	D6-150×150	m2	137	137.4	歩掛出典:林道 舗装工 溶接金網敷設
上層路盤工	再生クラッシュラン t=10cm	m2	160	159.6	
型枠工	一般型枠	m2	4	4.2	
目地板	瀝青繊維質目地板 t=10mm	m2	2	1.7	
(浄水場外柵工)					

数量計算書総括表

工 種	種 別	単位	計上数量	数 量	備 考
機械掘削	床堀	m3	2	2.3	
機械埋戻	土砂	m3	0.8	0.8	
土砂運搬		m3	2	1.5	舗装工にて計上
フェンス	PC-A1800	m	78	78.4	
立入防止柵設置	H=1800	m	78	78.4	
門扉	両開きW3000×H1800	組	1	1	
門扉設置	W3000×H1800	組	1	1	
基礎砕石工	再生砕石RC-40 t=10cm	m2	4	4	
型枠工	小型構造物	m2	16	16.2	
コンクリート工	小型構造物 18-8-25(20)	m3	0.8	0.8	
箱抜き(円形型枠)	φ125	m	1	1.0	
箱抜き(円形型枠)	φ90	m	14	13.7	
間詰モルタル	1:3	m3	0.1	0.1	
配水場付帯工					
(土工)					
機械掘削	床堀 現場制約有	m3	30	30.0	
土砂運搬		m3	30	30.0	舗装工にて計上
(配水場内舗装工)					
コンクリート工	18-8-25(20) t=10cm	m2	11	11.2	
溶接金網	D6-150×150	m2	100	99.8	
上層路盤工	再生クラッシュラン t=10cm	m2	112	111.6	
型枠工	一般型枠	m2	4	3.9	
目地板	瀝青繊維質目地板 t=10mm	m2	0.7	0.7	

数量計算書総括表

工 種	種 別	単位	計上数量	数 量	備 考
(配水場外柵工)					
機械掘削	床堀 現場制約有	m3	2	1.5	
機械埋戻	土砂 //	m3	0.5	0.5	
土砂運搬		m3	1	1.0	舗装工にて計上
フェンス	PC-A1800	m	48	47.5	
立入防止柵設置	H=1800	m	48	47.5	
門扉	両開きW3000×H1800	組	1	1	
門扉設置	W3000×H1800	組	1	1	
基礎碎石工	再生碎石RC-40 t=10cm	m2	3	2.6	
型枠工	小型構造物	m2	10	10.4	
コンクリート工	小型構造物 18-8-25(20)	m3	0.6	0.6	
箱抜き(円形型枠)	φ125	m	1	1.0	
箱抜き(円形型枠)	φ90	m	8	8.1	
間詰モルタル	1:3	m3	0.1	0.1	
付帯工(配管撤去工)					
(土工)					
人力掘削		m3	37.0	36.5	
人力埋戻		m3	39.0	39.4	
土砂運搬	L=3.5km以内	m3	7	7.4	
ルース積込		m3	7	7.4	
小車運搬	土砂 L=40～60m	m3	7	7.4	歩掛出典:林道 運搬工 小車運搬 小運搬距離:管延長(40m+56m) /2=48m程度
(舗装工)					
舗装版切断	Con t=10cm	m	1	1	
舗装版取壊		m2	7	7.0	A=10.0×0.7
小車運搬	Con殻 L=40～60m	m3	0.7	0.7	歩掛出典:林道 運搬工 小車運搬

数 量 計 算 書 総 括 表

工 種	種 別	単位	計上数量	数 量	備 考
殻積込	Con殻	m3	0.7	0.7	
舗装版運搬～処分	Con殻 L=8.0km以内	m3	0.7	0.7	7.0×0.1
型枠工	Con舗装	m2	1	1.1	(0.7+10.0)×0.1
小車運搬	セメント類 L=40～60m	t	2	2.3	歩掛出典:林道 運搬工 小車運搬 小運搬距離:管延長(40m+56m) /2=48m程度
舗装版復旧	18-8-25(20) 人力打設	m3	0.7	0.7	V=1m3、W=1.0×2.35≒2.3t
(配水管撤去工)					
鋳鉄管切断	DCIP φ 150	口	4	4.0	
鋳鉄管切断	DCIP φ 100	口	4	4.0	
K形杓帽	DCIP φ 150	組	2	2.0	
K形杓帽	DCIP φ 100	組	2	2.0	
杓継手工	φ 150	口	2	2.0	キャップ 特殊押輪割増率:4穴/8穴*30%=15%
杓継手工	φ 100	口	2	2.0	〃
既設管撤去切断	φ 150	口	16	16.0	(40.0m+56.0m)/標準6m
既設管撤去切断	φ 100	口	16	16.0	〃
撤去管吊上積込	φ 150 人力	m	96	96.0	40.0m+56.0m
撤去管吊上積込	φ 100 人力	m	96	96.0	〃
小車運搬	鋼材 L=40～60m	t	4	3.6	歩掛出典:林道 運搬工 小車運搬 W=(40.0m+56.0m)×0.022+ (40.0m+56.0m)×0.015
現場発生品運搬	クレーン装置付4t級 鋳鉄管 L=6.0km以下	t	4	3.6	
スクラップ	ヘビ-HS	t	4	3.6	
(導水管撤去工)					
鋼管切断	φ 100	箇所	2	2.0	
杓形キャップ	φ 100	個	1	1.0	
杓継手工	φ 100	口	1	1.0	キャップ

工 装 鋪 道 管 理

数 量 計 算 書

数量計算書

工 種 名 : 管理道舗装工

1.0式当り

種 別	規格・形状	計 算 式	単 位	数 量	備 考
(土工)					
機械掘削	床堀	舗装工数量計算書より、 $9.00 + 22.30 = 31.30$	m3	31.3	
機械埋戻	土砂	舗装工数量計算書より、 $135.70 = 135.70$	m3	135.7	
土砂運搬		$-(31.3 - 135.7 / 0.9) - 17.3 - 1.5 - 30.0 - 1.0 = 70.68$ (浄水場付帯工 土砂搬出分流用) (配水場付帯工 土砂搬出分流用)	m3	70.7	
(舗装工)					
不陸整正		舗装工数量計算書より、 $1689.00 = 1689.00$	m2	1689.0	
上層路盤工	再生クランラン t=10cm	舗装工数量計算書より、 $1689.00 + 223.60 = 1912.60$	m2	1912.6	
舗装工	再生密粒度As(13) t=4cm	舗装工数量計算書より、 $1689.00 = 1689.00$	m2	1689.0	
コンクリート工	18-8-25(20)	舗装工数量計算書より、 $223.60 = 223.60$			
	t=10cm	$223.60 \times 0.10 = 22.36$	m3	22.4	
はけ引き仕上げ		舗装工数量計算書より、 $223.60 = 223.60$	m2	223.6	
溶接金網	D6-150×150	舗装工数量計算書より、 $212.40 = 212.40$	m2	212.4	
目地板	歴青繊維質目地板 t=10mm	管理道平面図より、 設置N=4箇所×4.00 $16.00 \times 0.10 = 1.60$	m2	1.6	

舗装工数量計算書 (As)

測 点	単距離	AS1：上層路盤			AS1：アスファルト舗装			不陸整正			14K：床堀			B4-D：埋戻し			備 考
		幅	平均幅	面積	幅	平均幅	面積	幅	平均幅	面積	断面	平均断面	土量	断面	平均断面	土量	
NO. 0	0.000	8.7			8.7			8.7			0.9						
NO. 1	20.000	5.5	7.10	142.0	5.5	7.10	142.0	5.5	7.10	142.0	0.0	0.45	9.0		0.00	0.0	
BC. 1	7.507	4.0	4.75	35.7	4.0	4.75	35.7	4.0	4.75	35.7		0.00	0.0		0.00	0.0	
NO. 2	12.493	4.0	4.00	50.0	4.0	4.00	50.0	4.0	4.00	50.0		0.00	0.0	0.0	0.00	0.0	
BC. 2	10.967	3.5	3.75	41.1	3.5	3.75	41.1	3.5	3.75	41.1		0.00	0.0	0.1	0.05	2.1	
NO. 3	9.033	3.0	3.25	29.4	3.0	3.25	29.4	3.0	3.25	29.4		0.00	0.0	0.1	0.10	2.9	
SP. 2	10.658	3.0	3.00	32.0	3.0	3.00	32.0	3.0	3.00	32.0		0.00	0.0	0.1	0.10	3.2	
NO. 4	9.342	3.0	3.00	28.0	3.0	3.00	28.0	3.0	3.00	28.0		0.00	0.0	0.1	0.10	2.8	
EC. 2	10.348	3.0	3.00	31.0	3.0	3.00	31.0	3.0	3.00	31.0		0.00	0.0	0.1	0.10	3.1	
NO. 5	9.652	3.0	3.00	29.0	3.0	3.00	29.0	3.0	3.00	29.0		0.00	0.0	0.1	0.10	2.9	
NO. 6	20.000	3.0	3.00	60.0	3.0	3.00	60.0	3.0	3.00	60.0		0.00	0.0	0.1	0.10	6.0	
NO. 7	20.000	3.0	3.00	60.0	3.0	3.00	60.0	3.0	3.00	60.0		0.00	0.0	0.1	0.10	6.0	
NO. 8	20.000	3.0	3.00	60.0	3.0	3.00	60.0	3.0	3.00	60.0		0.00	0.0	0.1	0.10	6.0	
NO. 9	20.000	3.0	3.00	60.0	3.0	3.00	60.0	3.0	3.00	60.0		0.00	0.0	0.1	0.10	6.0	
NO. 10	20.000	3.0	3.00	60.0	3.0	3.00	60.0	3.0	3.00	60.0		0.00	0.0	0.1	0.10	6.0	
NO. 11	20.000	3.0	3.00	60.0	3.0	3.00	60.0	3.0	3.00	60.0		0.00	0.0	0.1	0.10	6.0	
NO. 12	20.000	3.5	3.25	65.0	3.5	3.25	65.0	3.5	3.25	65.0		0.00	0.0	0.1	0.10	6.5	
EC. 5	10.227	4.0	3.75	38.4	4.0	3.75	38.4	4.0	3.75	38.4		0.00	0.0	0.0	0.05	1.9	
					コンクリート舗装部 別途算出												
NO. 14	0.000	4.0			4.0			4.0						0.0			
BC. 8	10.675	3.5	3.75	40.0	3.5	3.75	40.0	3.5	3.75	40.0		0.00	0.0	0.1	0.05	2.0	
NO. 15	9.325	3.0	3.25	30.3	3.0	3.25	30.3	3.0	3.25	30.3		0.00	0.0	0.1	0.10	3.0	
NO. 16	20.000	3.0	3.00	60.0	3.0	3.00	60.0	3.0	3.00	60.0		0.00	0.0	0.1	0.10	6.0	
NO. 16 +10.00	10.000	3.0	3.00	30.0	3.0	3.00	30.0	3.0	3.00	30.0		0.00	0.0	0.1	0.10	3.0	
NO. 17	10.000	3.0	3.00	30.0	3.0	3.00	30.0	3.0	3.00	30.0		0.00	0.0	0.1	0.10	3.0	
NO. 18	20.000	3.0	3.00	60.0	3.0	3.00	60.0	3.0	3.00	60.0		0.00	0.0	0.1	0.10	6.0	
NO. 18 +10.00	10.000	3.0	3.00	30.0	3.0	3.00	30.0	3.0	3.00	30.0		0.00	0.0	0.1	0.10	3.0	
NO. 19	10.000	3.0	3.00	30.0	3.0	3.00	30.0	3.0	3.00	30.0		0.00	0.0	0.1	0.10	3.0	
NO. 20	20.000	3.0	3.00	60.0	3.0	3.00	60.0	3.0	3.00	60.0		0.00	0.0	0.1	0.10	6.0	
SP. 10	9.362	3.0	3.00	28.1	3.0	3.00	28.1	3.0	3.00	28.1		0.00	0.0	0.1	0.10	2.8	
NO. 21	10.638	3.0	3.00	31.9	3.0	3.00	31.9	3.0	3.00	31.9		0.00	0.0	0.1	0.10	3.2	
BC. 11	11.329	3.0	3.00	34.0	3.0	3.00	34.0	3.0	3.00	34.0		0.00	0.0	0.1	0.10	3.4	
NO. 22	8.671	3.0	3.00	26.0	3.0	3.00	26.0	3.0	3.00	26.0		0.00	0.0	0.1	0.10	2.6	
小 計	410.227			1371.9			1371.9			1371.9			9.0			108.4	

[illegible]

舗装工数量計算書 (Con)

測 点	距 離	14K ; 床堀			上層路盤工			溶接金網			はけ引き仕上げ			コンクリート舗装		
		断面	平均断面	土 量	幅	平均幅	面 積	幅	平均幅	面 積	幅	平均幅	面 積	幅	平均幅	面 積
EC.5 No.12+10.227		0.40			4.00			3.80			4.00			4.00		
No.13+4.00	13.773	0.40	0.40	5.5	4.00	4.00	55.1	3.80	3.80	52.3	4.00	4.00	55.1	4.00	4.00	55.1
No.13+9.00	5.000	0.40	0.40	2.0	4.00	4.00	20.0	3.80	3.80	19.0	4.00	4.00	20.0	4.00	4.00	20.0
No.14	11.000	0.40	0.40	4.4	4.00	4.00	44.0	3.80	3.80	41.8	4.00	4.00	44.0	4.00	4.00	44.0
EC.12 No.24+13.880		0.40			4.00			3.80			4.00			4.00		
No.25+5.00	11.120	0.40	0.40	4.4	4.00	4.00	44.5	3.80	3.80	42.3	4.00	4.00	44.5	4.00	4.00	44.5
No.26	15.000	0.40	0.40	6.0	4.00	4.00	60.0	3.80	3.80	57.0	4.00	4.00	60.0	4.00	4.00	60.0
	m			m3			m2			m2			m2			m2
合計	55.893			22.3			223.6			212.4			223.6			223.6

浄水場付帯工

数 量 計 算 書

数量計算書

工 種 名 : 浄水場付帯工事

1.0式当り

種 別	規格・形状	計 算 式	単 位	数 量	備 考
(浄水場内舗装工)					
コンクリート工	18-8-25 (20)	浄水場平面図より 面 積			
	t=10cm	31.67 × 9.98 = 316.07			
		控除数量(構内構造物)			
		滅菌室 3.22 × 4.57 × 1 = 14.72			
		犬走り 3.00 × 0.70 × 1 = 2.10			
		ろ過池 21.20 × 6.30 × 1 = 133.56			
		エアチャンバー 0.90 × 0.90 × 1 = 0.81			
		弁BOX (0.26 ^2 × π) / 4 × 14 = 0.74			
		電柱 (0.35 ^2 × π) / 4 × 1 = 0.10			
		ハントホール (0.60 ^2 × π) / 4 × 1 = 0.28			
		電磁流量計室 2.16 × 1.00 × 1 = 2.16			
		フェンス基礎 0.20 × 0.20 × 39 = 1.56			
		門扉基礎 0.40 × 0.40 × 2 = 0.32			
		舟形落し受付 0.30 × 0.30 × 1 = 0.09			
		計 = 156.44			
		場内面積 316.07 - 156.44 = 159.63			
		159.63 × 0.10 = 15.96	m3	16.0	
溶接金網	D6-150 × 150	浄水場平面図より 面 積			
		(31.67 - 0.20) × (9.98 - 0.20) = 307.78			
		控除数量(構内構造物+廻り10cm)			
		滅菌室 (3.22 + 0.20) × (4.57 + 0.20) × 1 = 16.31			
		犬走り (3.00 + 0.20) × (0.70 + 0.10) × 1 = 2.56			
		ろ過池 (21.20 + 0.20) × (6.30 + 0.20) × 1 = 139.10			
		エアチャンバー (0.90 + 0.20) × (0.90 + 0.20) × 1 = 1.21			
		弁BOX (0.46 ^2 × π) / 4 × 14 = 2.33			
		電柱 (0.55 ^2 × π) / 4 × 1 = 0.24			

数量計算書

工 種 名 : 浄水場付帯工事

1.0式当り

[illegible]

数量計算書

工 種 名 : 浄水場付帯工事

1.0式当り

種 別	規格・形状	計 算 式	単 位	数 量	備 考
(浄水場外柵工)					
機械掘削	床掘	門扉基礎 $0.50 \times 0.70 \times 2 + 0.20 \times 0.20 = 0.36$			
		フェンス基礎 $0.30 \times 0.55 \times 39 = 1.93$			
		舟形落し受付 $0.30 \times 0.30 \times 0.20 \times 1 = 0.02$			
		計 = 2.31	m3	2.3	
機械埋戻	土砂	門扉基礎 $(0.50 \times 0.40 \times 0.40 \times 2 = 0.07$			
		フェンス基礎 $(0.30 \times 0.20 \times 0.35 \times 39 = 0.68$			
		計 = 0.75	m3	0.8	
土砂運搬		$2.31 - 0.75 / 0.90 = 1.48$	m3	1.5	管理道舗装工 にて計上
フェンス	PC-A1800	浄水場平面図より 78.40	m	78.4	
立入防止柵設置	H=1800	78.40	m	78.4	
門扉	両開きW3000×H1800	浄水場平面図より 1.00	組	1.0	
門扉設置	W3000×H1800	1.00	組	1.0	
基礎砕石工	RC-40 t=10cm	門扉砕石 $0.50 \times 0.50 \times 2 = 0.50$			
		フェンス砕石 $0.30 \times 0.30 \times 39 = 3.51$			
		計 = 4.01	m2	4.0	
型枠工	□400×400×600	門扉基礎 $0.40 \times 0.60 \times 4 \times 2 = 1.92$			
(小型構造物)	□200×200×450	フェンス基礎 $0.20 \times 0.45 \times 4 \times 39 = 14.04$			
		舟形落し受付 $0.30 \times 0.20 \times 4 \times 1 = 0.24$			
		計 = 16.20	m2	16.2	

[illegible]

配水場付帯工

数 量 計 算 書

数量計算書

工 種 名 : 配水場付帯工

1.0式当り

種 別	規格・形状	計 算 式								単 位	数 量	備 考	
(土 工)		配水場横断面図より											
		測 点	距 離	機械掘削(床堀)			機械埋戻し(土砂)						
				面積	平均	土量	面積	平均	土量				
		横+0.00											
		横+7.20	7.20	2.6			0.0						
		横+19.50	12.30	1.3	1.95	23.99	0.0						
		横+23.50	4.00	1.7	1.50	6.00	0.0						
		合計	23.50			29.99							
機械掘削	床堀	上表より								= 29.99	m3	30.0	
機械埋戻	土砂	上表より								=	m3		
土砂運搬		29.99 - / 0.90								= 29.99	m3	30.0	管理道舗装工
													にて計上

数量計算書

工種名： 配水場付帯工

1.0式当り

種 別	規格・形状	計 算 式	単 位	数 量	備 考
(配水場内舗装工)					
コンクリート工	18-8-25 (20)	配水場平面図より 面 積			
	t=10cm	180.60 (CAD計測) = 180.60			
		控除数量(構内構造物)			
		配水池 10.60 × 6.10 × 1 = 64.66			
		連通管台 1.00 × 0.40 × 1 = 0.40			
		流量計室 1.40 × 1.00 × 1 = 1.40			
		流量変換器盤 0.65 × 0.75 × 1 = 0.49			
		弁BOX $(0.26^2 \times \pi) / 4 \times 9 = 0.74$			
		フェンス基礎 0.20 × 0.20 × 23 = 0.92			
		門扉基礎 0.40 × 0.40 × 2 = 0.32			
		舟形落し受付 0.30 × 0.30 × 1 = 0.09			
		計 = 69.02			
		場内面積 180.60 - 69.02 = 111.58			
		111.58 × 0.10 = 11.16	m3	11.2	
溶接金網	D6-150 × 150	浄水場平面図より 面 積			
		174.50 (CAD計測) = 174.50			
		控除数量(構内構造物+廻り10cm)			
		配水池 $(10.60 + 0.20) \times (6.10 + 0.20) \times 1 = 68.04$			
		連通管台 $(1.00 + 0.20) \times (0.40 + 0.10) \times 1 = 0.60$			
		流量計室 $(1.40 + 0.20) \times (1.00 + 0.20) \times 1 = 1.92$			
		流量変換器盤 $(0.65 + 0.20) \times (0.75 + 0.20) \times 1 = 0.81$			
		弁BOX $(0.46^2 \times \pi) / 4 \times 9 = 1.49$			
		フェンス基礎 $(0.20 + 0.20) \times (0.20 - 0.10) \times 23 = 0.92$			
		門扉基礎 $(0.40 + 0.20) \times (0.40 + 0.20) \times 2 = 0.72$			
		舟形落し受付 $(0.30 + 0.20) \times (0.30 + 0.10) \times 1 = 0.20$			
		計 = 74.70			
		174.50 - 74.70 = 99.80	m2	99.8	

数量計算書

工種名： 配水場付帯工

1.0式当り

[illegible]

数量計算書

工 種 名 : 配水場付帯工

1.0式当り

種 別	規格・形状	計 算 式	単 位	数 量	備 考
(配水場外柵工)					
機械掘削	床掘	門扉基礎 $0.50 \times 0.70 \times 2 + 0.20 \times 0.20 = 0.36$			
		フェンス基礎 $0.30 \times 0.55 \times 23 = 1.14$			
		舟形落とし受付 $0.30 \times 0.30 \times 0.20 \times 1 = 0.02$			
		計 = 1.52	m3	1.5	
機械埋戻	土砂	門扉基礎 $(0.50 \times 0.40 \times 2 = 0.07)$			
		フェンス基礎 $(0.30 \times 0.20 \times 0.35 \times 23 = 0.40)$			
		計 = 0.47	m3	0.5	
土砂運搬		$1.52 - 0.47 / 0.90 = 1.00$	m3	1.0	管理道舗装工 にて計上
フェンス	PC-A1800	配水場平面図より 47.50	m	47.5	
立入防止柵設置	H=1800	47.50	m	47.5	
門扉	両開きW3000×H1800	配水場平面図より 1.00	組	1.0	
門扉設置	W3000×H1800	1.00	組	1.0	
基礎砕石工	RC-40 t=10cm	門扉砕石 $0.50 \times 0.50 \times 2 = 0.50$			
		フェンス砕石 $0.30 \times 0.30 \times 23 = 2.07$			
		計 = 2.57	m2	2.6	
型枠工	□400×400×600	門扉基礎 $0.40 \times 0.60 \times 4 \times 2 = 1.92$			
(小型構造物)	□200×200×450	フェンス基礎 $0.20 \times 0.45 \times 4 \times 23 = 8.28$			
		舟形落とし受付 $0.30 \times 0.20 \times 4 \times 1 = 0.24$			
		計 = 10.44	m2	10.4	

[illegible]

1.0式当り

[illegible]

付帯工(配管撤去工)

数 量 計 算 書

土工計算書

測 点	点間距離	断面番号	人力掘削 土砂			人力埋戻 流用土			舗装版取壊 (Con:面積)			舗装版処分・復旧 (Con:体積)			土砂搬入 掘削量-埋戻量/0.9		
			断面	平均	数量	断面	平均	数量	断面	平均	数量	断面	平均	数量	断面	平均	数量
(配管撤去)																	
		①	0.51			0.54									-0.09		
	40.000	①	0.51	0.510	20.40	0.54	0.540	21.60							-0.09	-0.09	-3.60
		②	0.30			0.33									-0.07		
	46.000	②	0.30	0.300	13.80	0.33	0.330	15.18							-0.07	-0.07	-3.22
		③	0.23			0.26			0.70			0.07			-0.06		
	10.000	③	0.23	0.230	2.30	0.26	0.260	2.60	0.70	0.700	7.00	0.07	0.070	0.70	-0.06	-0.06	-0.60
合計					36.50			39.38			7.00			0.70			-7.42
改め					36.5			39.4			7.0			0.7			-7.4